

### MAINLINE

-----	50mm CL9 PVC
	50mm HANSEN FLUSHING VALVE HOUSED IN HR21419 VB
	50mm HANSEN ISOLATION VALVE HOUSED IN HR1419 VB
	APPROVED 2-WIRE CABLE INSTALLED IN 40mm MC CONDUIT WITH LIGHTNING ARRESTORS AS REQUIRED
	P1 ELECTRICAL PIT INSTALLED ON ALL CHANGE OF DIRECTION

### CONTROLLER

	RAINMAN CONTROLLER 2-WIRE HOUSED IN APPROVED CABINET
--	--

### LATERALS

-----	25mm CL9 PVC
-----	40mm CL9 PVC
-----	50mm CL9 PVC
-----	25mm CL9 PVC TREES
-----	50mm CL9 PVC TREES

### SLEEVES

-----	100mm CL12
-------	------------

### SPRINKLERS


	HUNTER I20SS #3 NOZZLE INSTALLED ON 20:300 ARTIC RISER
	HUNTER I20SS #6 NOZZLE INSTALLED ON 20:300 ARTIC RISER
	TORO 10' 570 MPR FIXED ARC NOZZLE 15:150mm ARTIC RISER
	TORO 12' 570 MPR FIXED ARC NOZZLE 15:150mm ARTIC RISER
	TORO 15' 570 MPR FIXED ARC NOZZLE 15:150mm ARTIC RISER
	360 DEGREE SPRAYS TO BE INSTALLED ON 300mm 570 POP-UPS
	ALL OTHER SPRAYS TO BE INSTALLED ON 100mm 570 POP-UPS

### BUBBLER TREE

	2 X HUNTER PCB-25 BUBBLER 150mm POP-UP INSTALLED ON FUNNY TUBE
	2 X HUNTER PCB-50 BUBBLER 150mm POP-UP INSTALLED ON FUNNY TUBE MATURE TRANSPLANT

### SOLENOID VALVES

	BERMAD 200S 50mm SOLENOID VALVE WITH DECODER TO SUITE FITTED WITH HANSON ISOLATION VALVE HOUSED IN HR1419VB
--	---



COMPANY:



SHEET DESCRIPTION:

IRRIGATION DESIGN  
ISSUED FOR TENDER

PROJECT:

SHIRE OF WAROONA  
DRAKESBROOK WEIR

REVISIONS:

Rev 2

Proposed  
Separable  
Portions

DATE:

20th February 2023

JOB NUMBER:

EOC-WDW-01

DRAWN BY:

PH

CHECKED BY:

N/A

SCALE:

1:500 @ A3

SHEET:

1 of 1